Ph: 26856360/61 26856071/585 Fax: 26856596

Date: - 05 /08 /2021

MAHANAND DAIRY

MAHARASHTRA RAJYA SAHAKARI DUDH MAHASANGH MARYADIT Unit No. 12, Aarey colony, Western Express Highway, Goregaon (E), Mumbai-400065

ENQUIRY Ref.No.MND/6/ENGG/ Insulation pipeline/2021-22 / 173 2

| TO | <u>O,</u> M/S. | | | | | |
|--|--------------------------|------------------------------------|------------------------|---|--------------|----------------------|
| | 141/0. | | | | | |
| m | ay please entioned he | be sent to us erein will not be | on or be considered | fer for the following items mention fore 17/08/2021 Quotation received. Quotation should be send in sellilled water / Milk Pipelines with M | ed after the | e due date |
| Description | | | | | | Quantity Required |
| Insulation for Chilled water / Milk Pipelines with Material | | | | | | |
| Details of job:- 1) Puff insulation with Aluminum cladding (24 Guage) with density-120 Sr. Pipe Line Running Meter Insulation Location | | | | | | One Job |
| No | Pipe Line Size | Running Meter | Insulation thickness | Location | | |
| 1 | 4" | 20 Meter | 75mm | Chiller to New Prepac | | |
| - 2 | 5" | 6 Meter | 75mm | Cold Room Passage | | |
| 3 | 2" | 61 Meter | 75mm | Cold Room Passage | | |
| 4 | 6" | 1.2 Meter | 75mm | Cold Room Passage | | |
| 5 | 8" | 1.2 Meter | 75mm | Glycol chiller | | |
| 2) N "(| O" Type Pipe Line | Running Meter | Insulation thickness | ding (24 Guage) with density-85 Armafie | x make class | |
| 1 | 2.5" | 262 Meter | 25mm | New Prepac & Old Prepac & chiller to O | ld prepac | |
| 2 | 3" | 23 Meter | 25mm | Old Prepac / New Prepac | - Propus | |
| . 3 | A" | 14 Motor | 25mm | Old Droppe / New Droppe | | |

- 25mm 3) Fixing of the new Insulation of the Pipeline & fitting after proper cleaning.
- 4) Fixing good quality 24 gauge Aluminum cladding width over the insulation.
- 5) Party should ensure that there will be no Temperature loss & Moisture leakage from the insulation after completion of job.

Old Prepac / New Prepac

- 6) Party can visit site for inspection, any queries or discussion, before submitting quotation
- 7) Party should use all safety equipment while carrying out the job.
- 8) MRDMM will not be responsible for any of the accident, if occured

TERMS AND CONDITIONS:-

22 Meter

- 1) The rate should be inclusive man and material, all taxes, ESIC, Transportation etc.
- 2) The job should be completed within 15 days from the date of job order.
- 3) Party should offer minimum 12 month guarantee for the job.
- 4) Payment will be made after satisfactorily completion of work. & satisfactorily trial run on load for one week.
- 5) Payment will be made as actual measurement of work done by the party.

